

GENERAL NOTES

- ▶ Refer to www.HMXpress.com for product information and manufacturing limitations on specific product types.
- ▶ Material illustrated in this submittal package will be fabricated only after formal approval by the architect, receipt of the approval for the hardware schedule and all required hardware templates.
- ▶ All doors and frames will be properly reinforced for surface mounted hardware as specified. Drilling and tapping for surface mounted hardware to be done in field by others.
- ▶ Function holes for lock sets and exit devices will be provided at factory. Any mounting holes will be drilled and/or tapped in field by others.
- ▶ All frames will be supplied with wall and floor anchors as specified on schedule.
- ▶ Field welding, grinding, finishing and attachment of field splices to be done by others.
- ▶ All standard type hardware will be located at the specified manufacturer's locations. Non-standard hardware must have specified locations. Hardware items such as rim exit panic devices and vertical rod exit devices will be located at manufacturer's suggested location unless otherwise specified.
- ▶ Installation of glass and glazing to be done in field by others.
- ▶ When hollow metal doors or frames are used in conjunction with aluminum, structural steel and/or wood products coordination of hardware locations will be the responsibility of the General Contractor.
- ▶ All frames in masonry construction are to be filled with grout where practical. If additives are used in mortar to decrease setting time, a bituminous coating should be applied to the inside of the jambs by the General Contractor.

HOLLOW METAL X PRESS

PAGE OF

JOB:

BUILDING:

CONTRACTOR:

CONTRACT #:

WRITTEN UP BY:

DATE: